

HOW TOMORROW MOVES



 **ARCADIS**

DIRECTED GROUNDWATER RECIRCULATIONFast Track To Site Closure

William Parry, CSX
Scott Murphy, Arcadis
Mark Klemmer, Arcadis
October 2015

HOW TOMORROW MOVES



AGENDA

- Project Background
- Site-Wide Remedial Activities
- Directed Groundwater Recirculation (DGR) Goals and Objectives
- DGR System Components
- Groundwater Monitoring/Performance
- Results



PROJECT BACKGROUND



- ➔ Adjacent Property
- ➔ Major Urban Thoroughfare
- ➔ Railroad Property



BACKGROUND

Assessment Process (Phase I, II, III)

- Completed ~ 4 years
- 377 soil borings
- 149 monitoring wells
- 1,346 soil samples
- 294 groundwater samples
- ~ 77 samples/acre

Site COCs

- Metals (Sb, Pb, Zn & Hg)
- PCBs
- CVOCs

Site Groundwater

- Trichloroethene
- Cis-1,2-dichloroethene
- Vinyl chloride



BACKGROUND (CONTINUED)

Challenge

Groundwater plume covers 12 acres and 3 properties

Driver


Pending Property Transfer

Objectives

- 60 percent mass removal in 6 months – property transfer
- GW Regulatory Standards in 15 months - Closure



SITE WIDE REMEDIAL ACTIVITIES/REMEDIATION AREAS



- Areas of Impact
 - GW ~ 12 acre plume
 - Soil - Disposal/Recycling of soils impacted with Petroleum, PCBs, CVOC, metals
- Remediation Technologies
 - Excavation
 - Electric Resistance Heating (ERH)
 - Directed Groundwater Recirculation (DGR)



SITE-WIDE GROUNDWATER REMEDIAL APPROACH

Directed Groundwater Recirculation (DGR)


- The primary method for treating groundwater within 12 acre boundary within the expedited timeframe
- Expedited removal compared to traditional pump and treat with sanitary sewer discharge
- Started April 22, 2015: currently in Month 7 as of October 22, 2015



DGR SYSTEM VISUALIZATION



DGR GOALS AND OBJECTIVES





DGR COMPONENTS

- DGR Project Installation Included

- 30,000 LF of HDPE
- 65,000 LF Electrical and Communication Wire
- 3 Directional Drill Borings
- 54 Injection Wells
- 6 Manifold Vaults and 3 Manifold Buildings
- 29 Extraction Wells
- 7,300 LF of Trench



MTS SYSTEM MONITORING






- DGR system monitored “real-time”
- 910 Input and Output Signals
- 2,940 HMI Tags
- 23 Nodes (Ethernet Connections)



GROUNDWATER MONITORING AND PERFORMANCE


Plume Boundaries

-  VOC Plume Prior to November 2014 Baseline
-  Flushing Zones Boundaries
-  ERH Footprint



Groundwater Analytical Data

-  Groundwater monitoring well




Groundwater Plumes




Note:
Groundwater analytical plumes represent most recent data for sampling locations;
however, only samples collected on designated dates are shown.



DGR REMOVAL EFFICIENCY





2014 BASELINE GROUNDWATER DATA



TCE

Cis-1,2-DCE

VC



Reduction: DGR: 31%; ERH -%



DGR: -62%; ERH -%



DGR: 11%; ERH -%


FEBRUARY 5-13, 2015 GROUNDWATER DATA



TCE

Cis-1,2-DCE

VC



Reduction: DGR: 45%; ERH -%



DGR: 37%; ERH -%



DGR: 33%; ERH -%

APRIL 2-3, 2015 GROUNDWATER DATA



TCE


Cis-1,2-DCE

VC

*Groundwater samples were not collected from the ERH zone during this event; ERH reduction values are from the April 15-17, 2015 groundwater sampling event



Reduction: DGR: 83%; ERH: 90%*



DGR: 65%; ERH: -20%*



DGR: 41%; ERH: -19%*

APRIL 30–MAY 1, 2015 GROUNDWATER DATA



TCE

Cis-1,2-DCE

VC

*Groundwater samples were not collected from the ERH zone during this event; ERH reduction values are from the April 15-17, 2015 groundwater sampling event



Reduction: DGR: 89%; ERH: 90%*



DGR: 64%; ERH: -20%*



DGR: 59%; ERH: -19%*

JUNE 1–JUNE 5, 2015 GROUNDWATER DATA



TCE


Cis-1,2-DCE

VC

*Groundwater samples were not collected from the ERH zone during this event; ERH reduction values are from the April 15-17, 2015 groundwater sampling event



Reduction: DGR: 88%; ERH: 90%*





DGR: 71%; ERH: -20%*



DGR: 65%; ERH: -19%*

JULY 1–JULY 2, 2015 GROUNDWATER DATA







JULY 30–AUGUST 3, 2015 GROUNDWATER DATA



TCE

Cis-1,2-DCE

VC



AUGUST 27–SEPTEMBER 1, 2015 GROUNDWATER DATA



CONCLUSION

Within **6 months** groundwater remediation progress is:

- 98% reduction in TCE
- 96% reduction in cis-1,2-DCE
- 80% reduction in VC

GW-2 standards met in shallow component of aquifer (still to be achieved in deeper component)

DGR is very effective at accelerating remedial objectives as compared to more traditional technologies

- ISCO forecast at 1.5 years, high cost
- In-situ bioremediation significantly longer time frame

Conventional pump and treat system strategies has historically meant long operation and maintenance period and years to achieve site closure.

DGR can be implemented to achieve aggressive treatment timetables and across very large plumes



HOW TOMORROW MOVES



 **ARCADIS**